

41 Perimeter Center East, Suite 250 Dunwoody, Georgia 30346 P (678) 382-6700 F (678) 382-6701 dunwoodyga.gov

### **MEMORANDUM**

**To:** Mayor and City Council

From: David Elliott

**Date:** August 24, 2015

Subject: Approval of Funding for Stormwater Pipe Repairs at 5631

**Woodsong Drive** 

#### **ITEM DESCRIPTION**

Approval of Funding for Stormwater Pipe Repairs at 5631 Woodsong Drive. The estimate for the rehabilitation is \$83,100, which includes a 10% contingency.

#### **BACKGROUND**

Needed pipe repairs were observed during a pre-paving survey completed by Public Works Staff. Woodsong Drive was paved earlier in 2015 and repairs are needed to this conveyance to prevent future settlement issues in the roadway and surrounding areas. The project involves the shotcrete replacement and reinforcement of 191' of 60" CMP. Two headwalls will also be stabilized during this project.

#### RECOMMENDED ACTION

Staff recommends approving \$83,100 in funding for Stormwater Culvert Repairs at 5631 Woodsong Drive.



41 Perimeter Center East, Suite 250 Dunwoody, Georgia 30346 P (678) 382-6700 F (678) 382-6701 dunwoodyga.gov











# PROSHOT CONCRETE, INC.

## SHOTCRETE CONTRACTORS & ENGINEERS

Telephone: 256.764.5941

4158 Musgrove Drive Florence, AL 35630 Fax: 256.764.5946

## **PROPOSAL**

Mr. David Elliott, P.E. Deputy Director of Stormwater 41 Perimeter Center East, Suite 250 Dunwoody, Georgia 30346 September 3, 2015

Re: RFP 2015-09 Shotcrete Restoration Services for Public Works Stormwater Construction Projects

60" CMP CULVERT REHABILITATION 5639 WOODSONG DRIVE	
Dear Mr. Elliott,	
We submit this proposal for City of Dunwoody 60" Culvert Reh	abilitation:
Item (7) 60-inch, rnd. liner, 5,000psi, 2inch thick, includes wire mesh reinforcement.	
191 LF@ \$325 per LF	\$62,075
Item (21) Seal End & Wing Wall, 2 Inch thick, 5,000psi mix includes coverage with wire mesh.	
15 SY @ \$198 per SY	\$ 2,970
Item (23) Clean all pipes and structures (solid debris removal on	ly)
7 CY @ \$1500 per CY (estimate)	\$10,500
Total for this Project	\$75,545
Respectfully, submitted, Proshot Concrete, Inc.  Patrick A. Mooney Senior Estimator/Project Manager	cc: Tony McDougle/Donnie Barnes Jacob Worley/Connie Dill
Accepted, 20	PROSHOT CONCRETE, INC.
By	Approved